

**Interested and eligible vendors are invited to submit quotations strictly as per the prescribed specifications mentioned below. For any clarification or assistance, please contact: 7866003362**

| S.No. | Description of the Work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Qty. |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|
| 1.    | Execution of the foundation of the High Mast Light pole, including excavation of the soil of 2.200mtr. X2.200 mtrX1,500 mtr, base with Single Brick Flat Solling of mtr.X1.600 mtr., with PCC (1:3:6) of 0.100 Mtr. thick of 1.600 Mtr. X 1.600 Mtr., base of the foundation 1.500 Mtr. X 1.500 Mtr.0.300 Mtr. and Pedestal footing with 0.750 Mtr. X 0.750 Mtr. X 1.275 Mtr. with reinforcement of base Jali 12 mm dia11 Nos of both side jail in top and bottom with chair12mm dia and 12 mm dia. main for pedestal of 12 Nos and 8 mm binder of 9 nos. with Shuttering and Plastering at project section of height of 0.250 Mtr. and filling earth filling in the remaining portion. As per the drawing attached in schedule. | 31   |
| 2.    | Supply and installation of Solar LED Light 50KW, 6 nos. and Solar Panel 170wp Solar Flood Light/ Street Light 50W, 6500K, IP 66 for Outdoor with 5 years warranty with Lithium Ferro Phosphate 60Ah battery, Solar panel and charger along with the luminaries' cast aluminium for a long life. specially designed pole mounting bracket allows different tilt angle later a land pole top mounting sun stay has highest efficiency of more than Make Light/Havells/Signify, Warranty 5 years against manufacturing defects from date of Supply.                                                                                                                                                                                 | 31   |
| 3.    | Supply and installation 12 Mtrs. GI Hexagonal Pole with 1HP motor, Winch - 350Kg, SS-316, 6mm Wire Rope, EPR - 5Cx 2.5Sq mm. Trailing Cable) Foundation Access and 1m6Arm Bracket with bottom dia. mm 360 mm top dia 150 mm, thickness 2.5 mm, (grade of steel 53555) single sharp welding with base plate (Dim.: 520 mm x440 mm x 16mm) with 1 mtr. 6 arm brackets with ring (Make - UTKARSH/ SHUBHAM/ BAJAJ) WITH WIND TUNNEL TEST CERTIFICATE etc.                                                                                                                                                                                                                                                                            | 31   |

